

" A 2 lane, 3 span bridge with improved immunity from flood events, replaces a low timber structure over the Coomera River, for Gold Coast City Council. "



**SCOPE:** 6 No. 1050 mm  $\varnothing$  to 9.9 m deep  
8 No. 1200 mm  $\varnothing$  to 6.5 m deep  
Cast In Place – Lined Bored Piles

**VALUE:** \$ 494,000.00

**EQUIPMENT:** Drill Rig Bauer BG 15  
Crawler Crane Manitowoc M8500

**CLIENT:** Queensland Bridge & Civil

**CLIENT CONTACT:** Jared Gibbards  
Project Engineer  
0437 119 265