

"A low-level causeway was replaced with new bridges over the Bohle River, on Townsville's Primary Northern approach, to accommodate Q50 flood events."



**SCOPE:** 209 No. 550 mm  $\varnothing$  to 24 m long Octagonal Precast Concrete Piles

**VALUE:** \$ 1,121,000.00

**EQUIPMENT:** Pile Rig Woltman THW 7528-D  
Hydraulic Hammer NAC 16T  
Crawler Crane Manitowoc M12000

**CLIENT:** BMD Constructions Pty Ltd

**CLIENT CONTACT:** Glen Langfeldt  
Project Manager  
0400 746 492