

" The causeway through the Mitchell River was damaged by flood which isolated communities and cattle stations, and was replaced by the Tablelands Regional Council, under the 'Betterment Fund'. "



SCOPE:	18 No. 550 mm ø to 26 m long Octagonal Precast Concrete Piles
VALUE:	\$ 277,000.00
EQUIPMENT:	Pile Rig Woltman THW 7528-D Hydraulic Hammer NAC 16T Crawler Crane Manitowoc M12000 Mobile Crane MAC 25t
CLIENT:	Pensar Civil Pty Ltd
CLIENT CONTACT:	Eric Walshe Project Manager 07 4031 5122